BURmastic® Composite Ply HT Green

Coated Trilaminate Reinforced Ply Sheet for Utilizing Recycled Material

FEATURES	BENEFITS
Multi-ply system	• Redundant waterproofing
Trilaminate reinforcement	• Superior strength and tear resistance for long term performance • Tough, durable protection
Continuous application	• Reduced labor costs • Reduced opportunity of application defects • Increases application simplicity
Helps Meet LEED Requirements	• Contains 14% pre-consumer recycled material

DESCRIPTION

BURmastic® Composite Ply HT Green is a polyester/glass scrim/glass mat trilaminate reinforcement coated with SBS Modified waterproofing asphalt. BURmastic Composite Ply HT Green has exceptional tensile and tear strength and contains 14% pre-consumer recycled material.

BASIC USES

BURmastic Composite Ply HT Green is designed as a ply sheet for application in multi-ply configurations over insulation boards and/or base sheets in the BURmastic cold process roof system. BURmastic Composite Ply HT Green can also be used as a hot, cold applied or mechanically attached base sheet or as the base membrane in the AlphaGuard® MT/MTS/BIO Fluid Applied Roof System. BURmastic Composite Ply HT Green exceeds the requirements of ASTM D 4601, Type II.

PACKAGING

Available in 3'x72' (915mm x 21.9m) rolls, 200 ft^2/roll (18.6m^2/roll). Sold by the pallet (20 rolls/pallet). 79 lbs/roll (35.8 kg).

GENERAL APPLICATION DATA

Roof replacement usually involves more complexities than new construction roofing. Often encountered are situations such as rust-ed/deteriorated decks, rotted wood components, rooftop equipment which cannot be moved or shut down, and numerous other conditions.

The following application information is designed to serve as a general guide. Your local Tremco Representative can prepare detailed specifications based upon your roof's conditions.

STRUCTURAL DECKS

Deck must be properly designed and structurally sound.

DRAINAGE

Ponding conditions are unacceptable and will adversely affect performance of any roofing system. If positive drainage does not exist, water removal must be facilitated by lowering drains and/or installing additional drains, tapered insulation, or lightweight cellular concrete.

INSULATION

Insulation must be dry and kept dry. No more insulation shall be installed than can be covered in that day.

APPLICATION

According to particular job specification, prepare surface to be covered:
- Replace areas of wet insulation, deteriorated deck and wood components.
- Install roof insulation, protection course, or base sheet.

Cold Process BUR: Starting at the low point of the roof, plan placement of BURmastic Composite Ply HT Green to ensure that water will flow over or along, but not against, exposed ply edges.

Continuous Lay Application:
- Apply cold process adhesive in a uniform and continuous application at a coverage rate of 2.5 to 3.0 gal/SQ (1.0 to 1.2 L/m2). Ply shall never touch ply.
- Using 2 men, align the full roll on the underlying ply line.
- Roll out the Composite Ply HT Green roll into the cold adhesive.

BURmastic® Composite Ply HT Green

APPLICATION
CONTINUED

- Broom the Composite Ply HT Green into place fully and heavily using a 32" wide broom. Do not use a felt rake, squeegee, roller, or other tool.
- Allow the Composite Ply HT Green roll to run true; if roll goes off line, cut the ply immediately and reset. Do not attempt to push or stretch roll back onto underlying line.

Cut and Relax: Alternately, the cut and relax method may be used:
- Cut 18' sections of Composite Ply HT and stack the sections for approx. 1 hour.
- Apply cold process adhesive at a coverage rate of 2.5 to 3.0 gal/SQ.
- Align and set the ply using 2 men; 1st man anchors the ply and 2nd man assures the ply is set on line.
- Broom the Composite Ply HT into place fully and heavily, using a 32" wide broom. Do not use a felt rake, squeegee, roller or other tool.

Three ply membrane: Start and finish roof membrane along edges, terminations, and projections, use starting/finishing strips – 12, 24, and 36" (305mm, 610mm, and 915mm) wide plies.

Install BURmastic Composite Ply in shingle fashion. Overlap starter strips 26" (660mm) with first ply, then overlap each succeeding ply 24-2/3" (625mm).

Four ply membrane: Start and finish roof membrane along edges, terminations, and projections, use starting/finishing strips – 9, 18, 27 and 36" (229mm, 457mm, 685mm, and 915mm) wide plies.

Install BURmastic Composite Ply HT Green in shingle fashion. Overlap starter strips 29" (750mm) with first ply, then overlap each succeeding ply 27-1/2" (698mm).

Base Sheet: Nail or embed a full width of BURmastic Composite Ply HT Green.

Side laps: 4" (100mm). End laps: 6" (150mm) minimum and staggered. Broom plies to assure complete contact. Extend all plies to top edges of all cants and cut off evenly. Overlap previous work 24" (610mm).

SURFACING OPTIONS

Smooth and aggregate surfacing options are available. Consult your local Tremco Representative for specific recommendations.

LIMITATIONS

- BURmastic Composite Ply HT Green is not intended to perform under ponding conditions. Positive drainage is required.
- BURmastic Composite Ply HT Green should not be exposed to solvents, oils or other contaminants harmful to asphaltic materials.
- Do not hot apply BURmastic Composite Ply HT Green in a multi-layer, shingle application.

PHYSICAL PROPERTIES

PROPERTY	TYPICAL VALUE	TEST METHOD
Weight	38 lb/ 100 ft^2 (1.8 g/m^2)	ASTM D 5147
Thickness	55 mils (1.4 mm)	ASTM D 5147
Tensile strength @ 77°F (25°C)	145 lbf/in (640N) MD, 135 lbf/in (600N) XD	ASTM D 5147
Pliability, 1/2 in.	No failures (13mm) radius	ASTM D 146
Mass of desaturated, mat, min.	3.0 lb/ 100 ft^2 (146 g/m^2)	ASTM D 228
Surfacing stabilizer, max.	65%	ASTM D 4601
Asphalt	10.0 lb/ 100 ft^2 (485g/m^2) minimum	ASTM D 228
Tear Strength @ 77°F (25°C)	225 lbf MD, 190 lbf XMD	ASTM D 5147

MAINTENANCE

Your local Tremco Roofing Sales Representative can provide you with effective maintenance procedures which may vary, depending upon specific conditions. Periodic inspections, early repairs and preventative maintenance are all part of a sound roof program.

PRECAUTIONS

Users must read container labels and Safety Data Sheets for health and safety precautions prior to use.

BURmastic® Composite Ply HT Green

TECHNICAL SUPPORT

Your local Tremco Roofing Sales Representative, working with the Technical Service Staff, can help analyze conditions and needs to develop recommendations for special applications.

TREMCO
Roofing & Building Maintenance

www.tremcoroofing.com
3735 Green Road
Beachwood, Ohio 44122
1.800.852.6013

220 Wicksteed Avenue
Toronto, Ontario, M4H 1G7
1.800.668.9879

Tremco Roofing and Building Maintenance is part of Tremco Construction Products Group.

0422